BRUHAT BANGALORE MAHANAGARA PALIKE

BILL OF QUANTITIES (BOQ)

Name of the work:-Patching Pot holes in main and cross roads of Kodigehalli, Tatanagara, Bhadrappa layout, Devinagara, Lottegollahalli, Muneshwaranagara and surroundings areas in ward no. 08

Sl. No.	Approved Qty.	Description	Unit	Issued to M/s. Nitin Enterprises	
				In Figures	In Words
1	167.74	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications	Sqm	86.92	Rupees Eighty Six and Ninety Two Paise Only
2	82.38	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifcations.	Cum	1768.08	Rupees One Thousand Seven Hundred Sixty Eight and Eight Paise Only
3	406.55	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm.KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, back filling the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2, Complete as per specifications.	Sqm	302.10	Rupees Three Hundred Two and Ten Paise Only
4	313.00	Lead and disposal of item No. 01 & road side debris	cum	106.00	Rupees One Hundred Six

For NITIIN ENTERPRISES
Proprietor

Signature of the Contractor

17/03

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

17/03